BANGALORE DIVISION.

Dated 5th April 1927.

FORM OF ADVERTISEMENT.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Bangalore Division, up to 12th April 1927, for restoring the Gabbadi Thavarekere and Kavalkere Tanks Registered No. 77 and 78 Kankanhalli Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1928.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rupees 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring the Gabbadi Thavarekere and Kavalkere Reg. Nos. 77 and 78 Kankanhalli Taluk in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of the same.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract Estimate for Restoring the Gabbadi Thavarekere and Kavalkere Tanks Registered Nos. 77 and 78 of Kankanhalli Taluk.

No.	Items of work	Per	Quantity
	KAVALKERE BUND.		
1	Clearing jungle	Grade	19
2	Earthwork	C.yd.	950
3	Turfing and trimming	Grade	19
4	New stone work	C.yd.	50
5	Old stone work with new jelly	,,	100
6	Providing new grade stones, numbering and painting etc. ...	No.	20
7	Do tap width stones	,,	20
8	Do bench mark stones	,,	2
9	Do registered No. stone	,,	1
	WASTE WEIR AT LEFT 120' LONG R. L. 50·00.		
1	Earthwork gravelly soil	C.yd.	1966
2	Dismantling the existing damaged masonry body wall ...	Lump	sum Rupees
3	Earthwork soft rocky soil	C.yd.	39
4	Burnt brick in surki mortar	C.ft.	2279
5	Plastering with surki mortar	Sqr.	17·74
6	Burnt stone slabs 6" thick dressed	S.ft.	267
7	Rough stone work new	C.yd.	122
8	Do old	,,	18
9	Jelly filling with single stones	,,	100
10	Providing bond slabs etc., to new and old wall and also putting earthen platform in front of masonry body wall from earth available in draft clay.	Lump	sum Rupees

No.	Items of work	Per	Quantity
	JACK BUND.		
1	Jungle clearing on both slopes of bund	Grade	6
2	Earthwork to bund	C.yd.	793
3	Turfing	Sqr.	769
4	Resetting old stone revetment with new jelly	C.yd.	50
5	Providing new grade stones including numbering and painting	No.	7
6	Do tap width stones	,,	7
	SLUICE.		
1	Constructing a regulating sluice	Lump	sum Rupees
	THAVAREKERE TANK BUND.		
1	Jungle clearing	Grade	18
2	Earthwork for road slopes	C.yd.	631
3	Turfing	Sqr.	500
4	New stone work	C.yd.	46
5	Old stone work	,,	50
6	Grade stones	No.	18
7	Registered No. stone	,,	1
8	B. M. stones	,,	1
9	Gauge stone	,,	1
	REPAIRING SLUICE.		
1	Front and rear head	Lump	sum Rupees

Dated 5th April 1927.

FORM OF ADVERTISEMENT.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Bangalore Division, up to 12th April 1927 for filling the breach of Sondekoppa Tank Reg. No. 214 of Nelamangala Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1928.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rupees 200 in cash or Government Promissory Notes, as earnest money, and be superscribed " Tender for filling the breach of Sondekoppa Tank Reg. No. 214 of Nelamangala Taluk in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of the same.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond ; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for filling the breach of Sondekoppa Tank Register No. 214 of Nelamangala Taluk.

No	Items of work	Per	Quantity
1	Removing soil and silt	C.yd.	97
2	Cutting grips in the breach gap and trenches in slopes of the main bund.	Lumsum	Rupees
3	Earthwork breach filling with watering and tamping, etc. ...	C.yd.	5,687
4	Earthwork excavation for masonry con. wall	C.yd.	17
5	Surki concrete foundation for con. wall	C.ft.	469
6	Puddle wall mixed with clay and gravel	C.yd.	983
7	Masonry con. wall	C.ft.	2,557
8	New stone work	C.yd.	389
9	Old stone work dismantling and collecting the scattered stones using new jelly etc.	C.yd.	50
11	Gravel backing	C.yd.	120
12	Turfing	S.yd.	1,160

FORM OF ADVERTISEMENT.

Dated 2nd April 1927.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M. on the 14th April 1927, for constructing a Middle School Building at Devanhalli. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1927.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Constructing a Middle School Building at Devanhalli in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders wil be returned.

Abstract estimate for constructing a Middle School building at Devanhalli, Bangalore District.

Serial No.	Items of work	Per	Quantities
1	Earth work excavation	C.yd.	59
2	Concrete stone jelly in chunam	C.ft.	611
3	Burnt stone in clay	,,	1,398
4	Burnt brick in clay	,,	3,002
5	Pillars with burnt brick in chunam cornice at top and bare plastering complete.	No.	5
6	Burnt stone slabs dressed and fixing	S.ft.	406
7	Chunam plastering	Sqr.	58·63
8	White and colour washings two coats	,,	58·63
9	Teak wood work wrought and put up	C.ft.	145·22
10	Roofing with 1st class Mangalore tiles on teak reepers ...	Sqr.	24·46
11	Ridge tiles set in mortar	R.ft.	118
12	Zinc sheet for valleys on teak planks 3' wide with chunam borders complete.	,,	82
13	Mortar bands over gable ends	,,	48
14	Do do small...	,,	66
15	Cornice at front gables 9"	...	48
16	Teak wood doors with panelled shutters hinges 9" bolts fixing etc., complete.	S.ft.	136
17	Teakwood windows with panelled shutters ¾" iron bars complete.	,,	189
18	Ventilators with expanded metal ¾" gauge teak frames 2" x 1½"	,,	63
19	Teakwood ornamental evave board ¾' x	...	42
20	Teakwood finials and terminates	No.	5
21	Chacolate painting two coats	Sqr.	8·37
22	Teakwood large board for front gable	S.ft.	20
23	False circular ventilators 2½' over side rooms with cornice etc., complete.	No.	2
24	Wood oiling and tarring complete two coats.	Sqr.	18·33
25	Cement pointing to basement	,,	4·04
26	Cornice over pillasters with base etc., ...	No.	4
27	Cuddapah slabs flooring on sand bed complete	Sqr.	15·20

R. W. SCALDWELL,
Executive Engineer.

MYSORE STATE TROOPS.

Notice, dated 1st April 1927.

Sealed tenders are invited for the right to cut and remove 2,165 trees as particularised below, marked for felling in the Hesserghatta Grass Farm. Tenders will be received till 2 P.M. on Monday the 25th April 1927 at the Chief Commandant's Office, Bangalore.

Kind of tree	Number of trees	Approximate yield
	Trees	720 tons of fuel and 100 c.ft. of Karijally timber
Casuarina	9	
Karijally	315	
Naibyala or Bilijally	1,658	
Mugali	20	
Hongey	32	
Other kinds	131	
Total ...	2,165	

1. Tenders should clearly show the rate at which the whole lot of trees will be purchased.
2. Every tenderer must deposit as earnest money a sum of Rs. 50 with his tender.
3. The sale is subject to confirmation by the Chief Commandant.